NOAA Fisheries Aquaculture Opportunity Area Updates






Aquaculture Opportunity Areas and Expanding U.S. Seafood

Expanding U.S. Seafood

As a complement to our wild-capture seafood, expanding domestic aquaculture is critical for economic and environmental resilience.

fisheries.noaa.gov/aquaculture





What have we done since May 7, 2020?





Now: Dec 2021

Coming soon!

Task:

Selected Gulf of Mexico and Southern CA as first two regions

Q&A, National and Regional rollouts; presentations & outreach

NCCOS data collection and modeling for siting analysis

RFI in October 2020; 5 listening sessions (3 national, 2 regional)

NCCOS draft Aquaculture Opportunity Atlas; peer review

Gulf of Mexico and Southern CA Atlases published (NEW!)

Consider selection of additional region(s), timing, resources


Combine public input, results of Atlas, and other information to identify NEPA alternatives


NOI to prepare PEIS, with preliminary AOA alternatives to consider

Begin stakeholder outreach and coordination in third region; RFI



AOA Atlases - Results and Next Steps











Aquaculture Opportunity Area Atlases: A Comprehensive Regional Marine Spatial Analysis

Marine Spatial Ecology Division
National Centers for Coastal Ocean Science
National Ocean Service







NOAA has built significant national spatial planning infrastructure!






Marine Spatial Data







Aquaculture Areas



MarineCadastre.gov

An Ocean of Information

A joint BOEM and NOAA initiative providing authoritative data to meet the needs of the offshore energy and marine planning communities.

All Ocean Pioneers Will Benefit









Atlases at a Glance

- Most comprehensive regional MSP ever conducted for U.S. federal waters
- More than 200 data layers utilized in each atlas
- Over 150 maps in each atlas that describe the ocean in new and unique ways
- Comprehensive stakeholder engagement
- Built new relationships and trust for NOAA science
- Created a framework for future AOAs and other ocean pioneering industries













Study Areas

Gulf of Mexico



Southern California



All types of aquaculture including shellfish, finfish, and algae.

Stakeholder Engagement

Stakeholder Meetings		
Gulf of Mexico and Southern California	Number	Attendees
Military	40	161
Natural Resources	157	787
Regional Planning Bodies	24	302
Industries	42	134
Navigation	12	45
Governance & Boundaries	66	256
Social & Cultural	14	50
Research Community	10	19
ENGOs	7	15
Human Health	23	79
Totals	395	1,848
Public Meetings	Date	
National AOA public listening session #1	11/5/20	
Southern CA AOA listening session	11/12/20	
Gulf of Mexico listening session	11/17/20	
National AOA public listening session #2	11/19/20	
Gulf of Mexico listening session (fishing stakeholders)	12/3/20	









Data Inventory Results

Data Layers	SoCal	GoMex
National Security	35	54
Natural Resources	77	92
Industry, Navigation, and Transportation	42	60
Fishing and Aquaculture	50	14
Total Layers	204	220

















Suitability Modeling

We identify areas of **highest opportunity** for aquaculture. Areas
that provide highest conservation
and lowest conflict with other users.








Categorical Data

Data Example	Score
Hard Bottom Habitat	0
Marine Protected Areas & Preserves	0.5
Habitat Area of Particular Concern	0.5
Deep Sea Corals	0
Oil and Gas Pipelines (500 m buffer)	0
Oil and Gas Wells (500 m buffer)	0
Shipwrecks (500 m buffer)	0
Unexploded Ordnance	0.5
Wastewater Discharge (500 m buffer)	0


Continuous Data

E.g., Fishing data, Vessel traffic, Wave climate



Cell scoring


Layer = not compatible = 0 Layer = may not be compatible = 0.5 No layer = 1





Modeling Process

Suitability Model



Cluster Analysis and Precision Siting Model


2)






1,000 acres

1,500 acres




Top scoring options






Southern California


Final Suitability





Cluster Analysis







7 clusters totally 60,347 acres
Only 2 clusters large enough for AOAs

1 cluster totally 4,665 acres



Precision Siting Model






N-1 cluster is 21,173 acres = 38 AOA options N-2 cluster is 11,679 acres = 246 AOA options

CN-1 cluster is 4,665 acres = 12 AOA options

296 total AOA options evaluated!




Top 10 Ranked AOA Options




118.5° W Central North Santa Monica Study Area Cluster 1 (CN-1) Marina Del Ray Selected Sites Final Cluster Inglewood CN-1 Selected Sites Principal Ports Manhattan Beach Pacific Ocean Hermosa Beach King Harbor Scale: 1:177.000 NAD83 CA Teale Albers rvice Layer Credits: Esri, HERE, Garmin, (c) Marine Spatial Ecology Division National Centers for Coastal Ocean Science CN-A = 1000 acres National Ocean Service CN-B = 500 acres

4.6 - 19 nm from nearest harbors Ventura Harbor, Santa Barbara Harbor, Oxnard

5.3 - 11.3 nm from nearest harbors Marina del Rey, King Harbor








Gulf of Mexico


Final Suitability






Cluster Analysis


West Region



Central Region



East Region



43 clusters **5,033** AOA options **339,755** acres

13 clusters 1,056 AOA options 93,220 acres

4 clusters 23,750 AOA options 722,900 acres

60 clusters 29,839 AOA Options Considered


Precision Siting Model

Top 9 AOA options identified A 30-nm dispersion rule applied to avoid overlap **13,500** acres


West Region

Totoria Gull of Mexico West Study Area AOA Option Selection West AOA Study Area Clusters AOA Options West AOA Study Area Clusters AOA Options

Central Region




East Region



Site	Size (acres)	Depth Average (m)	Closest Inlet (nm)
W-1	2,000	91	35
W-4	2,000	84	42
W-8	500	81	58

Site	Size (acres)	Depth Average (m)	Closest Inlet (nm)
C-3	2,000	61	72
C-11	2,000	82	41
C-13	500	62	5

Site	Size (acres)	Depth Average (m)	Closest Inlet (nm)
E-4	2,000	51	58
E-3	2,000	51	48
E-1	500	51	56






Atlas Story - Ship Parking Lots

A record number of cargo ships are stuck outside LA. What's happening?

Port complex of Los Angeles and Long Beach, already the busiest in the US, has seen major traffic this week as imports boom






What we learned....

- Overflow parking lots for ships may not be charted!
- Covid related supply chain backup issues
- Worked with NOAA Office of Coast Survey to chart
- Incorporated buffer areas in AOA analyses

Atlas Story - Fishing Data

- Deep collaboration with NMFS Sustainable Fisheries, Highly Migratory Species,
 Fishery Management Councils, State Agencies, Industry
- Assessed relative suitability based on fishing effort
- California model included 23 fisheries; 3 aquaculture operations
- Gulf of Mexico model included 6 fisheries; 1 aquaculture operation








"...we found that the analytical approach to spatial planning applied by the National Ocean Service (NOS) in that AOA initiative to be the most useful tool for supporting this critical decision-making." - SSA






Atlas Story - Protected Resources

- Developed novel scoring approach based on status and trends
- California model included 3 large whale species
- Gulf of Mexico included 8 species (whales, turtles, fish)





Status	Trend	Score	Converted scores for model
Endangered	declining, small population ² or both	9	0.10
Endangered	stable or unknown	8	0.20
Endangered	increasing	7	0.30
Threatened	Declining or unknown	6	0.40
Threatened	stable or increasing	5	0.50
Strategic MMPA Stock	declining or unknown	3	0.60
MMPA Stock	small population	2	0.70
MMPA Stock	large population	1	0.80



Thanks!






Round 1 Next Step: AOA Programmatic Environmental Impact Assessment (PEIS)

- Goal: Facilitate permitting efficiency through upfront environmental review
- Regionally led, HQ coordinated
- Areas that will be considered in the PEIS will be based on sources including:
 - NCCOS Atlas
 - Protected Resources, Sustainable Fisheries, and Habitat Conservation coordination
 - Public, stakeholder, agency input
- Input opportunities: scoping and public comment period



Multidisciplinary NEPA PEIS

Use the best available science in areas including those in our "NEPA flower," public and stakeholder input, and relevant regulations, laws, policies, to evaluate the beneficial and adverse impacts of siting aquaculture in a given area.



Round 2: Selecting AOA Region(s)

Interest in four areas:

- Western Pacific/Guam
- USVI and Puerto Rico
- Florida
- Alaska for shellfish and seaweed aquaculture (state and federal waters);
 Governor support and invitation into state waters









Round 2: Next Steps

- Determine resource availability, next steps, timeline
- Announce next region
- Begin stakeholder outreach and coordination
- Begin NCCOS data collection
- Work to prepare RFI for Round 2
- Plan for public comment period





